

A. Introduction

1. **Title:** **Reliability Coordination — Operations Planning**
2. **Number:** IRO-004-1
3. **Purpose:** Each Reliability Coordinator must conduct next-day reliability analyses for its Reliability Coordinator Area to ensure the Bulk Electric System can be operated reliably in anticipated normal and Contingency conditions. System studies must be conducted to highlight potential interface and other operating limits, including overloaded transmission lines and transformers, voltage and stability limits, etc. Plans must be developed to alleviate System Operating Limit (SOL) and Interconnection Reliability Operating Limit (IROL) violations.
4. **Applicability**
 - 4.1. Reliability Coordinators.
 - 4.2. Balancing Authorities.
 - 4.3. Transmission Operators.
 - 4.4. Transmission Service Providers.
 - 4.5. Transmission Owners.
 - 4.6. Generator Owners.
 - 4.7. Generator Operators.
 - 4.8. Load-Serving Entities.
5. **Effective Date:** November 1, 2006

B. Requirements

- R1.** Each Reliability Coordinator shall conduct next-day reliability analyses for its Reliability Coordinator Area to ensure that the Bulk Electric System can be operated reliably in anticipated normal and Contingency event conditions. The Reliability Coordinator shall conduct Contingency analysis studies to identify potential interface and other SOL and IROL violations, including overloaded transmission lines and transformers, voltage and stability limits, etc.
- R2.** Each Reliability Coordinator shall pay particular attention to parallel flows to ensure one Reliability Coordinator Area does not place an unacceptable or undue Burden on an adjacent Reliability Coordinator Area.
- R3.** Each Reliability Coordinator shall, in conjunction with its Transmission Operators and Balancing Authorities, develop action plans that may be required, including reconfiguration of the transmission system, re-dispatching of generation, reduction or curtailment of Interchange Transactions, or reducing load to return transmission loading to within acceptable SOLs or IROLs.
- R4.** Each Transmission Operator, Balancing Authority, Transmission Owner, Generator Owner, Generator Operator, and Load-Serving Entity in the Reliability Coordinator Area shall provide information required for system studies, such as critical facility status, Load, generation, operating reserve projections, and known Interchange Transactions. This information shall be available by 1200 Central Standard Time for the Eastern Interconnection and 1200 Pacific Standard Time for the Western Interconnection.
- R5.** Each Reliability Coordinator shall share the results of its system studies, when conditions warrant or upon request, with other Reliability Coordinators and with Transmission Operators,

Balancing Authorities, and Transmission Service Providers within its Reliability Coordinator Area. The Reliability Coordinator shall make study results available no later than 1500 Central Standard Time for the Eastern Interconnection and 1500 Pacific Standard Time for the Western Interconnection, unless circumstances warrant otherwise.

- R6.** If the results of these studies indicate potential SOL or IROL violations, the Reliability Coordinator shall direct its Transmission Operators, Balancing Authorities and Transmission Service Providers to take any necessary action the Reliability Coordinator deems appropriate to address the potential SOL or IROL violation.
- R7.** Each Transmission Operator, Balancing Authority, and Transmission Service Provider shall comply with the directives of its Reliability Coordinator based on the next day assessments in the same manner in which it would comply during real time operating events.

C. Measures

- M1.** Evidence that the Reliability Coordinator conducted next-day contingency analyses for its Reliability Coordinator Area to ensure that the Bulk Electric System could be operated reliably in anticipated normal and Contingency conditions.

D. Compliance

1. Compliance Monitoring Process

Entities will be selected for an on-site audit at least every three years. For a selected 30-day period in the previous three calendar months prior to the on site audit, Reliability Coordinators will be asked to provide documentation showing that next-day reliability analyses were conducted each day to ensure the bulk power system could be operated in anticipated normal and Contingency conditions; and that they identified potential interface and other operating limits including overloaded transmission lines and transformers, voltage and stability limits, etc.

1.1. Compliance Monitoring Responsibility

Self-Certification: Each Reliability Coordinator must annually self-certify compliance to its Regional Reliability Organization with the completion of the studies and action plans in Requirements R1, R2 and R3.

Exception Reporting: Reliability Coordinators will prepare a monthly report to the Regional Reliability Organization for each month that system studies were not conducted, indicating the dates that studies were not done and the reason why.

1.2. Compliance Monitoring Period and Reset Time Frame

One year without a violation from the time of the violation.

1.3. Data Retention

Documentation shall be available for 3 months to provide verification that system studies were performed as required.

1.4. Additional Compliance Information

None identified.

2. Levels of Non-Compliance

- 2.1. Level 1:** System studies were not conducted for one day in a calendar month and/or the action plans were not developed to maintain transmission loading within acceptable limits for potential interface and other IROL violations.

- 2.2. Level 2:** System studies were not conducted for 2–3 days in a calendar month and/or the action plans were not developed to maintain transmission loading within acceptable limits for potential interface and other IROL violations.
- 2.3. Level 3:** System studies were not conducted for 4–5 days in a calendar month and/or the action plans were not developed to maintain transmission loading within acceptable limits for potential interface and other IROL violations.
- 2.4. Level 4:** System studies were not conducted for more than 5 days in a calendar month and/or the action plans were not developed to maintain transmission loading within acceptable limits for potential interface and other IROL violations.

E. Regional Differences

None identified.

Version History

Version	Date	Action	Change Tracking
0	April 1, 2005	Effective Date	New
0	August 8, 2005	Removed “Proposed” from Effective Date	Errata